

Wood Shed

Material	Qty	Note	Cost	Total cost
✓ 4x6 - 14' treated	6	Front, 48" deep in ground	34.09	204.54
✓ 4x6 - 12' treated	6	Back	26.77	160.62
✓ 2x8 - 14'	4	Header	10.69	42.76
✓ 2x8 - 12'	4	Header	8.10	32.4
✓ 2x8 - 8'	4	Header	6.68	26.72
✓ 2.5" coated deck screw	400	200 for headers		19.19
✓ 2x6 - 14'	23	Truss	7.35	169.05
✓ 2x6 - 12'	6	Truss box (front/rear)	6.60	39.6
✓ 3.5" coated deck screw	2	400 for trusses only (265 per)	19.19	38.38
✓ Rafter to stud anchor	46	Without ends	0.84	38.64
✓ SPAX 3/8" x 5"	1	25 ct = 23.39 exterior grade		23.39
✓ Construction glue	3	For header lamination	2.26	6.78
✓ 8d 1.5" nails	460	For rafter to stud anchor (550 ct)		12.79
✓ Glue spreader				0.59
✓ Masons string	1	500'	5.39	5.39
✓ Chalk line	1		9.97	9.97
✓ 2x4 - 8'	4	Eves	2.52	10.08
✓ 2x4 - 12'	24	Horizontals	4.57	109.68
✓ 14' Tin (36") Pro-rib green L	11	Green	27.29	300.19
✓ 4x4 - 8'	4	Bracing	8.77	35.08
✓ Tin screws	500	1"		26.99
✓ SPAX 1/4" x 5"	2	50 Count	27.89	55.78
✓ 4" coated deck screw	250			23.48
✓ 2x6" rough 12'	18			72
✓ 2x6" rough 16'	20			100
TOTAL				1392.09
TOTAL + Tax				1469.62
Menards 11% Rebate				153.13
Out-of-pocket				1488.49
Dimensions				
Full cord (cu. ft.)	128			
Vol. between rows (%)	0.15			
Ht. of stack (ft.)	7.5			
Depth of shed (ft.)	12			
Length of shed (ft.)	32.00			
Total cord of shed	19.13			